BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of the Work: Improvements drain and Providing Covering slabs at Singapura Main Road Near Singapura Circle in ward No 11 (Kuvempunagara) in Vidyaranyapura Sub Division

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	331.30	**Earthwork excavation by manual means** in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	192.79	Rupees One Hundred Ninety Two and Seventy Nine Paise Only
2	48.29	Providing and laying in position plain cement concrete of **mix 1:4:8 with OPC cement @ 180 kgs with 40mm** and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5070.60	Rupees Five Thousand Seventy and Sixty Paise Only
3	124.24	Providing and laying cement concrete using 20mm and down size granite jelly of **ready mixed concrete (RMC)for R.C.C works** laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams etc complete as per specifications and directions of engineer in charge of the work	Cum	6332.04	Rupees Six Thousand Three Hundred Thirty Two and Four Paise Only
4	924.36	Providing and removing **centering, shuttering, strutting,** propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	**sqm**	306.72	Rupees Three Hundred Six and Seventy Two Paise Only

No of corrections - Nil

E.E. (B.P. DIV)

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
5	9.94	Providing **T .M.T steel reinforcement** for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 for TMT Bars Fe500 etc complete as per specifications and directions of engineer in charge of the work	Tonne	59327.91	Rupees Fifty Nine Thousand Three Hundred Twenty Seven and Ninety One Paise Only
6	41.40	Providing **precast slab of 250mm thick** including cost of all materials, labour, curing,transportation,loading unloading, etc.,complete as per the direction of engineer in charge- Data rate	Sqm	5125.00	Rupees Five Thousand One Hundred Twenty Five Only
7	330.00	Providing **precast slab of 100mm thick** including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge- Data rate	Sqm	1760.00	Rupees One Thousand Seven Hundred Sixty Only
8	611	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C 1:2:4 with top and bottom width 114 and 165mm repectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork curing, including, cost of all materials, labour hire charges of machinery, loading unloading, lead and lift, transportation etc complete as per specifications and directions of engineer in charge of the work	Nos	320.76	Rupees Three Hundred Twenty and Seventy Six Paise Only
9	123.75	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after throughtly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	27.00	Rupees Twenty Seven Only
10	123.75	Providing and applying spray painting in two coats (Excluding priming coat) over concrete / masonry / asbestos cement sheet / / plastered surfaces with lat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	68.04	Rupees Sixty Eight and Four Paise Only

No of corrections - Nil

5/01

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"

07.01.17